BEND SEWER INFRASTRUCTURE ADVISORY GROUP: MEETING 5

Immediate Challenges and Solutions

January 17, 2013



WELCOME AND INTRODUCTIONS

MEETING AGENDA / GOALS

- Review options for immediate solutions
- Advisory Group feedback







CITY OF BEND
COLLECTION SYSTEM MASTER PLAN



Immediate Term Alternatives

- Design & bid completed in one year.
- ✓ Involve pipes or pumps (preferably pipes).
- ✓ No environmental permits required.
- Comply with our existing DEQ WPCF permit.
- ✓ Do not require bond funding.

Solution Types

- 1. Increased capacity
- 2. Reroute flows
- 3. Diminish peak flows

Evaluation Criteria

- Cost basis
 - Design & construction cost only
 - 2011 CSMP
 (Addendum #4) unit costs escalated to 2013 dollars
 - Confirmed by recent bids
 - Planning level (engineering standard: -30%, +50%)

Assess the value of alternatives

Capacity

Certainty of Service

Overflow Risk

Ease of Construction

Operations, Performance and Flexibility


Introduction to Areas 5 and 3

- Area 5 / Solution 1: Gravity Sewer Upgrades
- Area 5 / Solution 2: Reconstruct Shevlin Lift Station
 + Upgrade Gravity Sewer
- Area 3 / Solution 1: Westside Pump 3 + Pump 4
- Area 3 / Solution 2: Westside Pump 3 + Pump 4 and Offline Storage
- COMBO / New Colorado Lift Station and Force Main to 2nd Street

Area 5
Solution 1

Gravity
Sewer
Upgrades


\$256,000



Area 5
Solution 2

Reconstruct
Shevlin Lift
Station +
Upgrade
Gravity Sewer


\$897,000



Area 3
Solution 1

Westside Pump 3 + Pump 4


\$701,000



Area 3 Solution 2

Westside
Pump 3 +
Pump 4
and
Offline
Storage

\$1,509,000



Areas 3 & 5 Option

COMBO

New
Colorado
Lift Station
and
Force Main
to 2nd
Street

\$3,890,000



Which solution do you like best and why?

Area 3
Solution 1
Westside PS
Pumps
\$701,000

5

Area 5
Solution 1
Gravity
Sewer
\$256,000

OR

Area 3
Solution 2
Westside
PS Pumps &
Storage
\$1,509,000



OR

Area 5
Solution 2
Reconstruct
Shevlin PS
\$897,000

or


COMBO

Areas 3 & 5

New Colorado Lift Station \$3,890,000


Which solution did you prefer for Area 5?

- Area 5, Solution 1: Gravity Sewer Upgrades
- 2. Area 5, Solution 2:
 Reconstruct Shevlin LS +
 Upgrade Gravity Sewer
- 3. No preference




Which solution did you prefer for Area 3?

- 1. Area 3, Solution 1: Westside Pump 3 + Pump 4
- 2. Area 3, Solution 2:Westside Pump 3 +Pump 4 + Offline Storage
- 3. No preference



Which solution did you prefer for Areas 5 and 3?

- 1. Mix of solutions for Areas 5 & 3
- 2. COMBO-New Colorado Lift Station, Force Main to 2nd Street
- 3. No preference




Introducing Area 2

- Solution 1: Gravity Sewer
- Solution 2: VFD Pumping
- Solution 6: North Force Main to Fred Meyer Rd.
- Solution 8: South Force Main to Fred Meyer Rd.
- Solution 3: South Force Main to Mervin Sampels
- Solution 4: South Force Main to Murray
- Solution 5: South Force Main to Butler Market

Area 2
Solution 1

Gravity Sewer

\$4,994,000



Area 2 Solution 2

VFD Pumping


\$8,287,000



Area 2 Solution 6

North Force
Main
to Fred
Meyer Rd.


\$5,342,000



Area 2 Solution 8

South Force Main to Fred Meyer Rd.


\$3,023,000



Area 2 Solution 3

South
Force Main
to Mervin
Sampels

\$9,513,000



Area 2 Solution 4

South Force Main to Murray

\$7,185,000



Area 2 Solution 5

South Force
Main to
Butler Market

\$5,733,000




Discussion

Which solution do you prefer and why?

- Solution 3: South Force Main to Mervin Sampels
- Solution 4: South Force Main to Murray
- Solution 5: South Force Main to Butler Market

Which solution did you prefer for Area 2?

- Solution 3 South Force Main to Mervin Sampels
- Solution 4 South Force Main to Murray
- 3. Solution 5 South Force Main to Butler Market
- 4. No preference



Recap Results: Advisory Group Feedback

- Area 5 Shevlin Lift Station
- Area 3 Westside Lift Station
- Area 2 Cascade Village Shopping Center

Immediate Solutions— Next Steps

SIAG recommendations to City Council January 30

Design March-December

Optimization results December

Construction 2014

Upcoming Advisory Group Meetings

February 7 Modeling and Optimization 101

February 21 Criteria and Lifecycle

March 7 Pumps, Pipes, Storage

March 21 Pumps, Pipes, Storage (Cont.)

April 4 Treatment Alternatives

April 18 Treatment Alternatives (Cont.)