

SOUTH THIRD STREET PEDESTRIAN IMPROVEMENT PROJECT INFORMATION



CITY OF BEND

Timeline

Construction Start – Mid to Late September 2016

Winter Shutdown – Mid November 2016 to Beginning of March 2017

Construction Complete – Late July 2017

Cost

Construction - \$2 million

Project Objective/Goal

Provide our community with a continuous and compliant pedestrian corridor along South Third Street between Wilson Avenue and Powers Road on both sides of the roadway.

Project Improvements

- Installation and rehabilitation of sidewalks
- Constructing new curb ramps that meet Americans with Disability Act (ADA) and Public Right-of-Way Accessibility Guidelines (PROWAG) requirements
- Replacing existing ramps that are out of ADA/PROWAG compliance
- Providing ADA/PROWAG compliant bus stop waiting pads for Cascades East Transit (CET) rider use
- Enhanced bicycle lanes with conversion of stormwater catch basin grates to curb inlet catch basins
- Replacing non-standard water meter boxes and service lines

Construction Specifics

- 10,000 Lineal feet of sidewalk
- 65 ADA compliant curb ramps
- 10 Bus stop waiting pads
 - CET Route 1
- Accessible Pedestrian Signals (APS) at every signalized crossing

General Construction Details

- Hours of construction activity will be 5 a.m. to 2 p.m.
- Access to all businesses will remain open
- Construction will occur on the east side of the roadway before the west side
- There will be single travel lane closures during active construction hours only

