


**NOTES:**

1. INSTALL PRE-FABRICATED FILTER INSERTS ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
2. FIELD FABRICATED INSERTS ARE NOT PERMITTED.
3. PRE-FABRICATED INSERTS WITH A PROVISION FOR OVERFLOW ARE REQUIRED AND ARE TO BE ACCOMPANIED BY ADDITIONAL BMPS TO PREVENT THE POTENTIAL OF SEDIMENTS ENTERING PROJECT STORM SYSTEMS.
4. PAIR WITH THE CURB LINE SEDIMENT ATTENUATEOR (SEE E-2C) AS REQUIRED.
5. INSPECT & MAINTENANCE:
  - 5.1. INSPECT WEEKLY AND DAILY DURING STORM EVENTS.
  - 5.2. CLEAN, OR REPLACE, INSERTS WHEN 50% OF THE SUMP AREA HAS FILLED WITH DEBRIS.
  - 5.3. CONTRACTOR IS RESPONSIBLE FOR REMOVING INSERTS AND PROPERLY DISPOSING OF ALL MATERIALS ONCE THE PROJECT HAS BEEN PERMANENTLY STABILIZED.

DRAWN CJH		<b>CITY OF BEND</b> STANDARD DRAWING 710 NW WALL ST., BEND, OREGON 97701	SCALE NTS
DIV EROSION			DATE 11/01/2024
REV DATE			APPR
		<b>GRATED INLET PREFABRICATED FILTER INSERT</b>	STD DWG E-2B
	CITY OF BEND		